GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

R&B Deptt.,- "Widening and Strengthening of Tekkali to SRK puram road (SKMD-058) (via) bannuvada from km.0/0 to 4/6 in Srikakulam District" - Administrative Sanction under Plan MDR - Accorded – Orders – Issued.

TRANSPORT, ROADS AND BUILDINGS (ROADS-III) DEPARTMENT

G.O.RT.No. 291 Dated: 22-06-2018
Read:

From the CE (R&B) MDR, & LWE, A.P., Letter No. 3165 /EE-1/DEE-1/AEE-1/2015-16, dated: 05-09-2017.

&&&&&

ORDER:-

Vide his letter read above, the Chief Engineer (R&B) MDR& LWE, A.P., has furnished estimate for the work of "Widening and Strengthening of Tekkali to SRK puram road (SKMD-058) (via) bannuvada from km.0/0 to 4/6 in Srikakulam District". The Chief Engineer (R&B) MDRs has stated that, the road is an important MDR in Tekkali constituency in Srikakulam District. The road originates at Km 8/0 of Nowpada – Meliaputti road and joins SRK Puram (via) Mododuvalasa, bannuvada. This road passes through Tekkali town limits from Km 0/0 to 0/8 and the stretch is busy market centre. The existing single lane road is not sufficient to free flow of present traffic and the vehicular traffic is facing much inconvenience to travel on the road and also causing accidents. The IRI of the road is varying from 5.27 to 7.57. Hence improvement of this stretch is necessary. He has furnished estimates for an amount of Rs.720.00 lakhs and requested for Administrative sanction.

2. In the circumstances reported by the Chief Engineer(R&B) MDR & LWE., A.P., in the reference read above and after careful examination of the matter, Government hereby accord Administrative Sanction for an amount of Rs.720.00 lakhs (Rupees Seven hundred and twenty lakh only) for the work "Widening and Strengthening of Tekkali to SRK puram road (SKMD-058) (via) bannuvada from km.0/0 to 4/6 in Srikakulam District" under Plan MDR.

3. The outcome of the project is as below:-

Sl.No.	Road No.	Total Length of the Road	Length to be improved	Out come	
				Item	Length
1	SKMD-058	4.600	4.600	1) Strengthening of the existing SL/IL carriageway to double lane and development of the widened two lane road to have good quality road surface (IRI) for the total carriageway of the double lane road.	4.600 Kms.
				2) Re construction of Pipe Culverts	15 Nos.
				3) Re construction of Slab Culverts	2 Nos.
				4) Construction of Protective Wall from km. 4/4 to 4/6	100 mtrs.

4. The amount sanctioned in the Para (2) above, shall be met from the Head of Account

P.T.O

"5054 Capital Outlay on Roads and Bridges – 04 District and Other Roads – MH.337 Road works– GH.11 State Development Schemes– SH (09) Major District Roads –530 Major Works – 531 Other Expenditure".

5. The Chief Engineer (R&B) MDR, Vijayawada, A.P., shall take further action accordingly.

6. This order issues with the concurrence of Finance (FMU.TR&B) Dept., vide their U.O.No. 17023/303/FMU-TR&B/2017, Dt.09.04.2018.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

NEERABH KUMAR PRASAD
SPECIAL CHIEF SECRETARY TO GOVERNMENT

To
The Chief Engineer (R&B) MDR, Vijayawada, A.P.,
Copy to:
The Finance (FMU.TR&B) Department, A.P.
The Director of Treasuries & Accounts, A.P., Vijayawada.
The Director of Works & Accounts, A.P., Vijayawada..
The Pay and Accounts Officer, Vijayawada /APAO Srikakulam District.
The District Treasury Officer, Srikakulam District.
The P.S. to Minister for R&B.
The P.S. to Spl.Chief. Secy., to Govt.
Sf/Sc.

//Forwarded By Order//

SECTION OFFICER